

 EXTENSION TO NEYRIZ 66/20 KV SUBSTATION Price List NRZ-ANJ-SS-SPC-151-Z			جدول مقادیر و قیمت‌های بخش تامین تجهیزات و عملیات نصب، تست و راه اندازی توسعه دو فیدر خروجی ۲۰ کیلوولت پست ۶۶/۲۰ کیلوولت نیریز							
ITEM	DESCRIPTION	UNIT	QTY (1)	UNIT PRICE FOR PURCHASE EQUIPMENT RIALS (2)	UNIT PRICE FOR TRANSPORTATION INSURANCE & ETC RIALS (3)	UNIT PRICE FOR ERECTION & OMMISIONING, TEST RIALS (4)	TOTAL COST FOR PURCHASE EQUIPMENT (RIALS) (5)=1*2	TOTAL COST FOR TRANSPORTATION INSURANCE & ETC (RIALS) (6)=1*3	TOTAL COST FOR COMMISIONING & TEST (RIALS) (7)=1*4	TOTAL COST (RIALS) (8)=(5+6+7)
1	20KV DRAWABLE METAL CLAD PANELS CONSISTING OF VACCUM CIRCUIT BREAKER, CURRENT TRANSFORMERS, EARTHING SWITCHE, CORE BALANCE CT, ALL PROTECTION RELAYS, METERING & INDICATING DEVICES, ENERGY METER, DISCREPANCY AND OTHER SWITCHES, PUSH BUTTONS, POSITION INDICATORS, NEON INDICATING LAMP AND ETC. FOR OUTGOING FEEDERS AS PER DRAWINGS & SPECIFICATION	SET	2							
2	ADAPTOR METAL CLAD PANELS FOR CONNECTION NEW MV PANELS TO EXISTING MV PANELS AS PER DRAWINGS & SPECIFICATION	SET	2							
3	EARTHING GRID, RISERES, CLAMPS, JOINTS, CONNECTIONS, BARS, ETC NDEED FOR CONNECTING ALL EQUIPMENT, STRUCTURES, PANELS, ... TO GRONDING MESH AS PER DRAWINGS & SPECIFICATION	LOT	1							
4	POWER CABLE 24KV, XLPE, WITH MIN. (1×185) mm2 SINGLE CORE, COPPER CONDUCTOR AS PER DRAWINGS & SPECIFICATION	M	2000							
5	SINGLE PHASE INDOOR TYPE 24KV CABLE SEALING ENDS AND ACCESSORIES FOR 185mm2 XLPE COPPER CABLES	NO.	12							
6	SINGLE PHASE OUTDOOR TYPE 24KV CABLE SEALING ENDS AND ACCESSORIES FOR 185mm2 XLPE COPPER CABLES	NO.	12							
7	CONTROL, PROTECTION, CT, CVT AND POWER CABLE	LOT	1							
8	MODIFICATION CONTROL SYSTEM AS PER DRAWINGS & SPECIFICATION & REQUIRMENTS	LOT	1							
9	ENERGY METTER	SET	2							
10	MODEM APN	SET	1							
11	MODIFICATION OF HMI SYSTEM	LOT	1							
12	MODIFICATION OF SCADA INTERFACE PANEL	LOT	1							
13	FIBER OPTIC CABLE	LOT	1							
14	SWITCH AND OTHER EQUIPMENT RELATED TO COMMUNICATION ISSUES IS NECESSARY BASED ON THE OF IRAN GRID MANAGEMENT CO (IGMC) AND INFORMATION RELATED TO THE DTT SIGNAL	LOT	1							
15	EQUIPMENTS LABEL & SUBSTATION SIGNS	LOT	1							
16	CIVIL WORKS FOR MODIFICATION OF 20kv SWITCHGEAR BUILDING AS PER DRAWINGS, SPECIFICATIONS & REQUIREMENTS	LOT	1							
17	INDOOR & OUTDOOR CABLE TRENCH AS PER DRAWINGS, SPECIFICATIONS & REQUIREMENTS	LOT	1							

 EXTENSION TO NEYRIZ 66/20 KV SUBSTATION Price List NRZ-ANJ-SS-SPC-151-Z				جدول مقادیر و قیمت‌های بخش تامین تجهیزات و عملیات نصب، تست و راه اندازی توسعه دو فیدر خروجی ۲۰ کیلوولت پست ۶۶/۲۰ کیلوولت نیریز						 آیا نیروی جم شرکت مهندسیین مشاور (سهایی خاص)
ITEM	DESCRIPTION	UNIT	QTY (1)	UNIT PRICE FOR PURCHASE EQUIPMENT RIALS (2)	UNIT PRICE FOR TRANSPORTATION INSURANCE & ETC RIALS (3)	UNIT PRICE FOR ERECTION & OMMISIONING, TEST RIALS (4)	TOTAL COST FOR PURCHASE EQUIPMENT (RIALS) (5)=1*2	TOTAL COST FOR TRANSPORTATION INSURANCE & ETC (RIALS) (6)=1*3	TOTAL COST FOR COMMISIONING & TEST (RIALS) (7)=1*4	TOTAL COST (RIALS) (8)=(5+6+7)
18	ELECTRICAL UTILITIES WORKS FOR BUILDING EXTENSION	L O T	1							
19	MECHANICAL UTILITIES WORKS FOR BUILDING EXTENSION	L O T	1							
20	SITE PREPARATION	L O T	1							
21	SITE MOBILZATION	L O T	1							
22	ENGINEERING WORKS	L O T	1							
23	OTHER WORKS	L O T	1							
Total Price:										